BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:-Maintenance and repairs of Chainlink fencing in ward No:04 of Yelahanka Satellite Town Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	Removing and resetting of footpath slab (P.No 255, I.No 37.56)	Sqm	761.63	114.48	Rupees one hundred fourteen and paise forty eight only
2	KSRB 2.6 : Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with lead upto 50m, and lift upto 1.5 m. complete as per specifications. specification. No. KBS (P.No 6, I.No 2.13)	Cum	112.66	1666.68	Rupees one thousand nine hundred sixty six and paise sixty eight only
3	KSRB 14.6-2 : Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed and compacting with plate vibrator etc as per specification &direction of the engineer in charge of the work.(Item no14.6, Page no98, PWD SR 2014-15)	Sqm	751.09	876.62	Rupees eight hundred seventy six and paise sixty two only
4	Removing and resetting of kerb stones	Mtr	800.40	58.32	Rupees fifty eight and paise thirty two only
5	Providing fixing RCC precast solid concrete kerb stone made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., (Size 450x150x500)	Nos	1067.00	345.00	Rupees three hundred forty five and paise sixty only
6	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, la	Sqm	600.24	669.92	Rupees six hundred sixty nine and paise ninety two only
7	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials as per specifications.		298.58	316.94	Rupees three hundred sixteen and paise ninety four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate in Words
8	Supplying and fixing M.S. Rectangular Poles made but of 2 equal angles of 65 x 65 x 6 mm welded together and fixed inCC (1:2:4) with 2 Nos. 16 mm dia M. S. hold fast rods each of length 25 cms. including cost of all materials, cutting, bending scaffolding etc as per specifications.	Kmtr	150.40	1093.92	Rupees one thousand ninety three and paise ninety two only
9	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and weldin	Kgs	749.70	92.22	Rupees ninety two and paise twenty two only
10	KSRB-15-17.6: Providing and applying painting two coats (excluding priming coat on new wood surface and / war wood faced surface with enamul paint to give an even shade cleaning of surface of all dirt, dust and forign matte, Sand preparing including cost of maeritals, complete as per specification)	Sqm	28134.76	82.68	Rupees eighty two and paise sixty eight only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Executive Engineer,
Welfare Division,
BBMP, Bangalore.